


# The ESS In-Kind model

# ess


## With a lot of help from our friends



# **ESS Project**

## A world leading spallation source






Parameter	Value
Proton beam power	5 MW
Proton beam energy	2 GeV
Peak current	62.5 mA
Pulse length	2.86 ms
Rep rate	14 Hz
Duty factor	4 %
Bunching frequency	352.21 MHz

# Beam Diagnostics

# ess

## Beam modes and pulse structure



Device	Туре	IS	LEBT	RFQ	MEBT	DTL	SPK	MBL	HBL	HEBT	A2T	DmpL	Total
Faraday cup	Current		1		1	2							4
ВСМ		1	1	1	2	5		1	1	2	3	2	19
Fast BCM					2								2
Doppler			1										1
ВРМ	Parasitic transverse				7	15	14	9	21	16	12	4	98
Non-invasive profile			2		2		1	3	1		1		10
Imaging	Parasitic target/dump transverse										2	1	3
Grid											1		1
Aperture											3	1	4
Emittance	Non-parasitic		1		1								2
Bunch shape					1		1						2
WS					3		3	3	1	3	1		14
BLM	Loss				4	47	78	38	86	51	38	6	348

# Proton beam

## Beam modes and pulse structure



### 2 stage chopping Source < 75 mA ≤ 3000 µs ~100 µs ≤ 2860 µs LEBT (chopper) 6-65 mA ~0.1+20 µs ≤ 2860 µs ~0.1 µs REQ 6-63 mA **MEBT** (chopper) 6-62.5 mA

~0.01 µs



< 1 uA to DTL4


~0.01 µs

≤ 2860 µs

## **NCL** Overview



- ISRC & LEBT
  - DC beam > 70 mA @ 75 keV
  - Chop pulse, diagnose, focus & match for RFQ
- RFQ
  - 4.5 m, 5 segments, 4-vane, accelerate to 3.62 MeV
- MEBT
  - Diagnose beam, fine chop, collimate, match for DTL
- DTL
  - 5 tanks, accelerate to 90 MeV (74 MeV after DTL4)
  - Temporary beam stop & shield wall in place of 5th tank



# Tunnel configuration

NCL commissioning











Throughout commissioning



## Throughout commissioning




• January 31st Start of RF commissioning in DTL

## Throughout commissioning

ess

• January 31st Start of RF commissioning in DTL

April 18<sup>th</sup> First beam extracted from ion source



## Throughout commissioning



- January 31<sup>st</sup> Start of RF commissioning in DTL
- April 18<sup>th</sup> First beam extracted from ion source
- April 19th First beam to MEBT FC





11 / 36

## Throughout commissioning



- January 31<sup>st</sup> Start of RF commissioning in DTL
- April 18<sup>th</sup> First beam extracted from ion source
- April 19<sup>th</sup> First beam to MEBT FC
- April 20<sup>th</sup> First beam through DTL4





## Throughout commissioning



- January 31<sup>st</sup> Start of RF commissioning in DTL
- April 18<sup>th</sup> First beam extracted from ion source
- April 19<sup>th</sup> First beam to MEBT FC
- April 20<sup>th</sup> First beam through DTL4
- May 4<sup>th</sup> First beam seen by DTL4 FC

### Throughout commissioning




- January 31<sup>st</sup> Start of RF commissioning in DTL
- April 18<sup>th</sup> First beam extracted from ion source
- April 19<sup>th</sup> First beam to MEBT FC
- April 20<sup>th</sup> First beam through DTL4
- May 4<sup>th</sup> First beam seen by DTL4 FC
- May 30<sup>th</sup> First 50us beam through DTL4

### Throughout commissioning



- January 31<sup>st</sup> Start of RF commissioning in DTL
- April 18<sup>th</sup> First beam extracted from ion source
- April 19<sup>th</sup> First beam to MEBT FC
- April 20<sup>th</sup> First beam through DTL4
- May 4<sup>th</sup> First beam seen by DTL4 FC
- May 30<sup>th</sup> First 50us beam through DTL4
- July 6<sup>th</sup> First 50us, 62.5 mA beam through DTL4






ning ir 1 ion so

- may ou i noi ouus deam unougn DTL4

 July 6<sup>th</sup> First 50us, 62.5 mA beam through DTL4



11 / 36

### Throughout commissioning



- January 31<sup>st</sup> Start of RF commissioning in DTL
- April 18<sup>th</sup> First beam extracted from ion source
- April 19<sup>th</sup> First beam to MEBT FC
- April 20<sup>th</sup> First beam through DTL4
- May 4<sup>th</sup> First beam seen by DTL4 FC
- May 30<sup>th</sup> First 50us beam through DTL4
- July 6<sup>th</sup> First 50us, 62.5 mA beam through DTL4
- July 14<sup>th</sup> End of beam commissioning to DTL4

### Throughout commissioning




- January 31<sup>st</sup> Start of RF commissioning in DTL
- April 18<sup>th</sup> First beam extracted from ion source
- April 19<sup>th</sup> First beam to MEBT FC
- April 20<sup>th</sup> First beam through DTL4
- May 4<sup>th</sup> First beam seen by DTL4 FC
- May 30<sup>th</sup> First 50us beam through DTL4
- July 6<sup>th</sup> First 50us, 62.5 mA beam through DTL4
- July 14<sup>th</sup> End of beam commissioning to DTL4
- August 1<sup>st</sup> Last day of beam commissioning run

# RF Commissioning

A major non-beam goal of the commmissioning

- Overall goal for DTLs was >12hrs with >95% RF at nominal parameters
- Started January 31<sup>st</sup> (first beam planned mid April)
- One DT replaced in DTL1 after 2022 commissioning
- Quickly reached nominal field for short pulse
- First half of March all DTLs close to reach goals
- Second half of March DTL2&3 RF windows arching






Francesco Grespan/INFN

# Beam Availability





- Excellent support from the OPs crew
- Beam availability good for early stage
- Some interlock/trip analysis work to be done for our 95% availability goal





Arkadiusz Gorzawski


## Ion Source extraction

### Repeller issue











- Large initial divergence and emittance observed during the source+LEBT commissioning in 2019.
- Discovered source repeller was disconnected (maintenance Jan 2022)
- Significantly improved model consistency!
- Data from 2019 less relevant





# RFQ Characterization




#### **MEBT TOF - FBPM**








- Time-of-flight confirmed ~3.6 MeV
- Voltage scan matched well to reconstructed model
- Transmission match expectations from model (96-98%), solenoid scan pattern differ



# **Trajectory Correction**



- Total of 20 BPM's in the NCL
- RF noise challenges on certain DTL BPMs
- Polarity checks BPMs, correctors
- Ignoring a few BPMs we got a good RMS
- We use SVD for matrix inversion



#### Natalia Milas

# Phase Scans

#### 3 MEBT bunchers and 4 DTL tanks



- 3 bunchers
- 4 DTL tanks (3 new)
- 20 BPMs
- Manual set up still achievable
  - For SCL 146 cavities → automation essential
- Frequency jump between Spoke-MBL
  - Amplitude match particularly important

#### DTL scans

- First (few) internal BPM(s) → sine-like response
- Here we focus on online modelling & fitting
- For more details on DTL measurements, see
   M. Comunian et al. THBP07


#### **Buncher scans**

- Closest BPM may observe RF noise
- Model based (OpenXAL) BPM response fitting
- "Turning off" with time delay is fast
- Fully detuning is time consuming
- Aim for scans w/o needing to detune
  - Lowering current
  - Short pulse


## **Buncher Phase Scans**



- Weighted sum of fit to expected model response of all BPMs
- BPMs close to buncher may see RF noise (orange)
- Automated fit in ~1 min per buncher



#### Buncher 2 scan




## **Buncher Phase Scans**

#### To detune or not to detune



- Compared to measurements with fully detuned buncher 2
- BPM3 & 5 gave -110.4 & -111.2 deg
- Compared to -110.7 deg with no detuning
- Amplitude still to be fully verified
- Low current and short pulse seems reasonable

But ...




# Phase/current dependence




Significant current dependence on beam phase out of RFQ

- Iris cuts of transverse tails → change energy distribution?
- Less severe when current is lowered by Sol2
- RF phase scan at low current, operations at full current
- Effect dampens with energy but emittance blows up.
- Depends on ISrc HV. (Energy mismatch?)

Note: requirements on the set phase/amp is 1-deg & 1%






Ryoichi Miyamoto


## DTL Phase Scans

### DTL Wizard application

ess

- Dr. A. Shishlo from SNS visited us for 3 months
- Focus on DTL phase scan strategy
- Developed a new application based on PyORBIT
- Together with Dr. S. Zhukov transitioned PyORBIT from Python2 to Python3 github.com/PyORBIT-Collaboration/PyORBIT3
- Evaluated fitting strategy
  - Suggest BPM1 for first guess, BPM2 for precise fitting
- Model improvement identified: calibration of cavity amplitude should take into account the longitudinal bunch size





$$\rho(\phi) = \frac{1}{\sqrt{2\pi\sigma}} e^{-\frac{(\phi - \phi_0)^2}{2\sigma^2}}$$

$$\langle \Delta W \rangle = \int \rho(\phi) \cdot qV_0 \cdot TTF \cdot \cos(\phi_0) d\phi = qV_0 \cdot TTF \cdot e^{-\frac{\sigma^2}{2}} \cdot \cos(\phi_0)$$





J. Müller - TUC2C2

# **DTL Phase Scans**

## Fitting to internal BPM1 only








ESS NCL COMMISSIONING RESULTS 23/36

# **DTL Phase Scans**

# ess

## Fitting to internal BPM1 + BPM2



Improved fitting BPM1+2: Use predominantly BPM2 data


ESS NCL COMMISSIONING RESULTS 25/36

# DTL1 Phase Scans


## Fitting to internal BPM1 + BPM2



### BPM1



Generally DTL1 harder to fit - matching issues?



ESS NCL COMMISSIONING RESULTS 26/36


# DTL1 Phase Scans

## Reproducibility?



Shift	DTL1	DTL2	DTL3	DTL4
20230530B	2.89/-131.8	3.0/-101.4	3.25/-198.1	<b>2.58</b> /75.8
20230602B	N/A	3.09/-95.1	3.24/-162.9	2.84/101.0
20230602B	N/A	3.11/-99.0	3.27/-161.6	2.84/101.3
20230626A	2.85/-131.3	3.08/-96.2	3.22/-159.6	2.86/109.1
20230711A	<b>2.91</b> /-152.4	3.08/-115.2	3.22/-179.6	2.85/88.01
20230711A	<b>2.65</b> /-155.9	3.09/-122.9	3.22/-180.3	2.84/90.2

# Selecting a different reference pickup?




Francesco Grespan/INFN

ESS NCL COMMISSIONING RESULTS 27/36

## **DTL Transmission**



- Transmission in DTL ~100%
- Lose beam into DTL1
  - Input conditions?
  - Alignment issues?
  - Beam phase dependency on current in RFQ?



#### Natalia Milas

# EMU H data




We had horizontal EMU available last days

Technical hurdles and resource limitations

Results fit very well with model predictions!

- very encouraging but we need more data




**Daniel Noll** 

# EMU H data


## Background subtraction







- Gaussian distributed
- Fit Gaussian to background and subtract
- Then apply flat signal cut
- ESS design 0.25 mm mrad out of RFQ



**Daniel Noll** 

# Full NCL installed



End of September we had the entire NCL installed

A particular congratulations and thanks to the INFN Legnaro colleagues!



# Summary



- Nominal, 50us beam transported through DTL4
- Trajectory correction worked well
- Phase scan strategy works well
  - Seems precise, uncertain accuracy?
- Transverse measurement encouraging
- More attention needed...
  - Matching into DTL1
  - Phase out of RFQ
  - Source characterization
  - 50 us → 2860 us
  - •
- A successful commissioning campaign
  - Many systems come together
  - Learn how to operate
  - Learn where attention is needed