

PAUL SCHERRER INSTITUT




Joachim Grillenberger :: Large Research Facilities :: Paul Scherrer Institute


# The High Intensity Proton Accelerator Facility Status and Perspectives

FB 2023

# High Intensity Proton Accelerator 50<sup>th</sup> Anniversary in 2024



# High Intensity Proton Accelerator Facility




## Scheduled Beam Time

User operation: 5000h  
 Beam development: 350h  
 User visits per year: 1800

# 590 MeV Ring Cyclotron at PSI

in operation since 49 years (19.2.1974 first muons)



**Beam energy:** 590 MeV  
**Beam current:** 2.4 mA  
**Beam power:** 1.4 MW  
**Relative losses:**  $1.2 \cdot 10^{-4}$   
**Single turn extraction**

4 cavities (50.63 MHz): 850 kVp  
 1 Flattop (151 MHz): 550 kVp

Harmonic number: 6

Number of turns: 186  
 8 sector magnets: 0.6 – 0.9 T

$R_{in}$ : 2.1 m

$R_{out}$ : 4.5 m


**Energy efficiency:**

$$\eta_{acc} = \frac{P_{beam}}{P_{Grid}} = \frac{1.42 \text{ MW}}{8 \text{ MW}} = 0.18$$



# History of the Beam Power


## Designed for 60 kW



**Ultimate goal is 3.0 mA**  
**Corresponds to 1.8 MW**

3 resonators

# Empirical Power Scaling Law



Losses scale with

- (turn separation at the extraction)<sup>-1</sup>  $\propto N$
- Charge density in the cyclotron  $\propto N$
- Acceleration time  $\propto N$

# Copper Cavities at PSI



- $f = 50.6 \text{ MHz}$
- $U_{\text{max}} = 1.2 \text{ MV}$  (presently 850 kVp)
- $Q = 4.8 \cdot 10^4$
- Transfer of up to 400 kW power to the beam per cavity

Last Cu-cavity commissioned in 2008




Wall plug to beam efficiency:

- AC/DC: 90%
- DC/RF: 64%
- RF/beam: 55%
- **All over: 32%**

# History of the Beam Power

Designed for 60 kW




**Ultimate goal is 3.0 mA**  
**Corresponds to 1.8 MW**

3 resonators



# Injector 2 Cyclotron

Commissioned in 1985



870 keV  
vertical injection


- beam energy: **72 MeV**
- max. beam current: **2.7 mA**
- 4 sector Magnets: 0.33 – 0.36 T
- weight per magnet: 180 tons
- 2 resonators: 50.63 MHz
- 2 flattop resonators: 150 MHz
- harmonic number: 10
- injection radius: 0.4 m
- extraction radius: 3.5 m
- **80 turns**

Beam power: 72 MV • 2.7 mA = **194 kW**

Ongoing upgrade project for **3.0 mA** and **reliability**

1995 the operation observed in Injector 2


- the same extraction rate without Flattops (accidentally switched off)
- a higher extraction rate with reversed phase (accelerating mode, less turns)



Explained by the «vortex effect»

M. M. Gordon, The longitudinal space charge effect and energy resolution, In McIlroy[47], 425pp. 305–317 (1969)



S. Adam, Space charge effect in cyclotrons - from simulations to insights, In Comell[48], 439pp. 446–448 (1995)



- Vortex motion stabilizes the bunch
- Space charge couples longitudinal and horizontal motion
- Longitudinal focusing (weak though)

# Injector 2 – Upgrade

- Goal:** reduce the number of turns from **83 to 60 for 3 mA** ( $n^3$  – law)  
 $\Rightarrow$  Increase energy gain per turn  $\Rightarrow$  Increase acceleration voltage



150 MHz Flattops not needed (Vortex Effect)  
 double energy gain per turn

**60 instead of 83 turns -> 3.0 mA according to  $I \simeq \frac{1}{n^3}$  where n = number of turns**

**Already installed 2018**

# Injector 2 – Upgrade



New Resonator 2

Installed 20.02.2018

resonance frequency	50.6328 MHz
accelerating voltage	400 keV @ $R_{out}$
dissipated power	50kW @ 400kVp
Q	24'500
Tuning range	200 kHz
material cavity RF-wall	EN AW 1050
material structure	EN AW 5083
cooling water flow	15 m <sup>3</sup> /h
dimension	5.6 x 3.3 x 3 m
weight	7000 kg

Resonator	type	material	frequency	gap voltage	Wall losses in cavity	incident power @ 2.4 mA Beam
1 & 3	Double gap cavity	aluminum	50 MHz	~ 420 kVp	~ 150 kW	~ 225 kW
2 & 4	Flattop cavity	aluminum	150 MHz	~ 31 kVp	~ 5 kW	~ 14 kW
2 & 4 new	Single gap cavity	aluminum	50 MHz	~ 400 kVp @ extraction	~ 50 kW	~ 100 kW

# Status Injector 2 – Upgrade

## The new 50 MHz Resonators


### Resonator 2:

- Installed in Injector 2 Cyclotron in 2018
- **No tuner up to 2023**


served very well as a vacuum chamber.....

### Resonator 4:


- In test stand for tuner and power tests
- Treated with Aquadag (multipactoring)



Resonator 4: treated with Aquadag




Resonator 2 installed in Injector 2





Resonator 4 in test bunker  
**Installation in 2024**

# Tuner for new Resonators tested in Resonator 4




- Tuners show abrasion caused by contact springs
- Tests with different materials, different spring preload, ... failed
- New concept was necessary

Finger contacts between  
vaccum vessel and plunger




Strong abrasion  
of contacts

# New Tuner Concept



Tuners




- No spring contacts
- New vacuum vessel Al instead of steel
- Additional cooling channel on vacuum vessel
- Optimized geometry to reduce RF leaking into vessel
- New plunger with improved cooling channels

# Installation of tuners during Shutdown 2023



Installation team




Coaxial transmission line (RL100-230, Spinner)  
New tuners installed


**6. September 2023 first beam through Ring with 1 mA**



# Resonator 2 Commissioning




— Resonator 2 at 400 kV  
 — Resonator 2 detuned




# Resonator 2 Commissioning

Peaks shift as desired  $\longrightarrow$  higher energy gain per turn




# Resonator 2 Commissioning



# Injector 2 – Upgrade Amplifiers



- 2. Goal:** Higher RF-voltage for new Resonators 2 + 4
- 3. Goal:** replace outdated amplifier chains for resonators 1 + 3



# Resonator 4

## Amplifier control unit

3<sup>rd</sup> goal became priority 1



Reduced beam current for 6 months  
1.8 mA instead of 2 mA

- Unit failed in June 2022
- 40 years old / no documentation
- No spare parts
- Amplifier replaced with two SSAs BBL200-A10000
- Will be used as drivers for Res. 1-4



2 X BBL200-A10000 @152 MHz

# Injector 2 – Upgrade Amplifiers

- 2. Goal:** Higher RF-voltage for new Resonators 2 + 4
- 3. Goal:** replace outdated amplifier chains for resonators 1 + 3

RF annex



400 kW stages  
Thales RS2074




Anode PS  
15 kV / 40A  
Ampegon



**Commissioning:** Res 2 in 2023, Res 4 in 2024, Res 1 & 3 in 2025

# High Intensity Proton Accelerator Facility Cockcroft – Walton



Cockcroft-Walton  
870 keV, 30 mA

Ring Cyclotron  
590 MeV, 2.4 mA


Injektor 2-Cyclotron  
72 MeV, 2.7 mA

Currently limited to 2mA  
3 Resonator operation

# Cockcroft – Walton 870 keV, 30 mA



Cockcroft-Walton with 810 kV platform and acceleration tube  
ECR-source very reliable (>99%)



2020: HV breakdown due to scorched acrylic glas




SF<sub>6</sub> disposal



polishing



Recurring: burnt fibre optics



different supplier or laser transmission






Defect transformer in microwave amplifier  
No more support  
**New solid state version**





# Status of the Ring Cyclotron



**Current routine operation at 2 mA**  
Reason: Injector 2 – Upgrade

- Vacuum improved (rad. hard In sealings)






- Electrostatic Elements shielded (RF)
- Cu-Cavities ready for 3.0 mA
- RF-Amplifiers need upgrade for 1.8 MW
- New long radial probe

# Long Radial Probe Ring cyclotron Renewal Project

Not available since 2012 but  
important for beam dynamics


- New mechanical drive
- New wire fork



Wires still burn out even with RF only  
Studies with C-nano tubes ongoing

# 150 MHz Flattop Cavity (1979)

72 MeV beam ↓



Probe RRL I just showed




3<sup>rd</sup> harmonic «flattop» cavity

- 151 MHz
- 550 kV (11% of main voltage)
- $Q = 28000$
- Gap = 0.25 m




- Larger phase acceptance ( $40^\circ$  instead of  $9^\circ$ )
- Factor of 10 less losses at extraction

# Röntgen Emission Cavity 5






● Ionisation chambers

# Multipactoring Flattop Aquadag Coating




abrasion



- Plasma ignition in sector magnet above 450 kV flattop voltage
- 20 kW of RF-power “leak” into vacuum chamber
- **Cooling insufficient for  $I > 2.4 \text{ mA} / U_{\text{cav}} > 550 \text{ kV/p}$**

**Aquadag to suppress secondary electron emission**

# Empirical Scaling Law by W. Joho<sup>1</sup>




Losses scale with

- (turn separation at the extraction)<sup>-1</sup>  $\propto N$
- Charge density in the cyclotron  $\propto N$
- Acceleration time  $\propto N$



[1] W. Joho, High intensity problems in cyclotrons, Proceedings of the 9<sup>th</sup> International Conference on Cyclotron and their Applications, pp. 337–47. Les Editions de Physique, BP 112, 91402 Orsay (France), ISBN 978-3-95450-160-1 (1981).

# Longitudinal Dynamics


- variation of accelerating voltage over the bunch length **increases energy spread**
- thus a third harmonic flattop resonator is used to **compensate the curvature** of the cavity voltage w.r.t. time (apparently no vortex effect in Ring cyclotron)
- optimum condition:  $U_{\text{tot}} = U_0 \left( \cos \omega t - \frac{1}{9} \cos 3\omega t \right)$



# New 150 MHz Flattop Cavity for 3.0 mA




- Material choice: pure Aluminum
- New shape of the electrodes (increase peak shunt impedance)
- Improved cooling for 140 kW dissipated power
- New coupler design (ongoing)



Multipactoring studies



# Availability of the Accelerator Facility



**High availability is of uttermost importance for the users**  
**Secondary particle yield comes second**

# Target E – Upgrades

- Life-time of ball bearings 6 months (1 failure per year)
- Life-time of motor 3 years




Exchange flask




Hotcell

~48h



1-2% availability

# Target E – Upgrades




Standard 40 mm Target E

## Challenges

- 50 kW on Target E ⇒ Rotation 1 Hz (**bearings**)
- Cooling (1700 K) ⇒ Radiation, Cu-shielding cooled
- Temperature resistant material ⇒ Polycrystalline graphite
- Thermal stress (deformation) ⇒ Spokes (thermal expansion)  
Slits in wheel


## Bearings were the neuralgic spot




New ball bearings with solid state WS<sub>2</sub> lubricant  
by S. Makimura (J-Parc) & KOYO®  
Installed in 2019

**No target failure during user operation  
since December 2019**

# Target E – Upgrades




30 – 50% increase in surface muon rate  
(measurement and simulation agree)



Beam position monitoring by  
current transmission measurement

# Steps Towards a Higher Efficiency SINQ – Upgrade 2019

- Replacement of neutron guides
- Optimization of instruments
- Optimization of D<sub>2</sub>O moderator geometry




- measured flux gains ranging from 2–30 depending on the instrument
- signal to noise ratio increased by a factor of 6
- **The Accelerator's uptime and beam intensity remain the primary driving forces!**


# Steps Towards a Higher Performance Accelerator part

## Increase Beam Power to 1.8 MW

- Understand and reduce losses
- More diagnostics and simulations
- Finish Injector 2 Upgrade (by 2025)
- Increase gap voltage in Ring ( $n^{-3}$  – law)
  - More powerful RF-amplifiers (SSA?)
  - new flattop system
- **Well trained operators and more beam development (A.I. does not exist...)**



- The PSI accelerator has already delivered a 1.4 MW beam in CW mode
- Major performance steps achieved by RF-upgrades
- The average availability now is 90%
- Number of short trips (<5 min) is >10 per day
- Modular design allows for fast and save repair (< 2days, 4h average)
- **Energy efficiency is 0.18 (bare accelerator)**
- High demand of Neutron Sources
- Since 2020 new neutron guides/monochromators (2–30 more neutrons)
- **New project IMPACT is on its way**
- Operation until 2030+



<https://www.psi.ch/en/impact>

CDR: <https://www.dora.lib4ri.ch/psi/islandora/object/psi:41209>


**We have to/want to prepare for another 20-30 years of operation**

**Infrastructure, conventional systems, cooling, hotcells, etc are in good condition**


# 10 Year Upgrade Plan

- **Electronics and Control System**

- Replacement of CAMAC-based system
- New Firmware and Control system integration
- interlock integration and level adaption



started -2026





- **RF – Renewal and/or Upgrade**

- new Flattop
- Renewal / Upgrade of RF-amplifiers (SSD)

Injector 2 -2025  
 prestudies -2030  
 strategic decision

- **Magnet Renewal and Spares**

- many coils over 50 years old
- Bending magnets critical stock



inventory  
 stock keeping

- **Diagnostics**

- Fast Wire Scanners (beam current 3 mA)
- BPMs in 590 MeV beamline
- Profile monitors in 590 MeV beamline
- Radial Probes (new wire material, e.g., nano tubes)

started -2026  
 strategic  
 started -2030  
 started -2026  
 promising

- **Power Supplies**

- On-Going and recurring project
- New design with Silicon Carbide

running -2026

- **Vacuum System**

recurring



## My thanks go to

- Markus Schneider
- My Colleagues
- Your attention!

Alps: 30 – 150 Million years

